Serial No.	Items of work	Unit	Rate	Quantity	Rate to be quoted in	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
9	Teakwood ventilators with iron bars and glazed shutters of $1\frac{1}{4}$" thick including 2 coats of silicate painting	S.ft.	1 10 0	46		
10	Teakwood wrought and put up with two coats wood-oiling, etc.	C.ft.	4 8 0	89·54		
11	Roofing with 1st class Mangalore Tiles on teak reepers with two coats of wood-oiling to the reepers ..	Sqr.	23 0 0	10·56		
12	Ridge Tiles set in cement mortar with cement pointing	R.ft.	0 7 0	44		
13	Flooring with $1\frac{1}{2}$" of cement concrete over 3" of stone jelly concrete in lime mortar and 1" of cement plaster mixed with red ochre and finished smooth with lines cut to tile pattern	Sqr.	22 0 0	6·00		
14	Plastering with mortar $\frac{3}{4}$" thick ..	,,	2 12 0	27·72		
15	White washing two coats	,,	0 3 9	32·24		
16	Colour washing outside	,,	0 4 9	12·76		
17	Mortar bands over roof including plastering, etc., complete	R.ft.	0 4 0	44		
18	Cement pointing to basement ..	Sqr.	3 0 0	1·80		
19	Providing and fixing cave boards of teakwood 1" thick	R.ft.	0 8 0	140		
20	Providing and fixing ventilating tiles..	No.	1 12 0	8		
21	Dismantling the existing wall for fixing a door	C.ft.	0 0 6	92		
22	Cement concrete slab below door ..	,,	0 10 0	2		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, JOG FALLS PROJECT DIVISION, (Camp) BANGALORE.

Notification dated 12th October 1938.

1. Sealed tenders in triplicate will be received at the Office of the Executive Engineer, Jog Falls Project Division, (Camp) Bangalore, superscribed with the name of the work mentioned below.

2. The plans connected with the work may be seen at the office of the undersigned at all working hours. The copy, if required, will be made available on payment of Rs. 3 per set.

3. The tenders should be drawn up strictly in conformity with the specifications furnished, writing out the rates at which each item of work will be executed in figures as well as in words, failing which no cognisance will be taken of the tender. No items other than those noted in the statement should be included as the items cover provision for all sundries, repairs to damaged masonry and painting.

4. The materials to be used on the work should be of best quality conforming to the specifications of this department and B. S. or A. I. E. E. specification. Mention should also be made of the manufacture and the catalogue numbers of the materials offered. Teakwood planks to be used on the work should be free from knot, cracks and well seasoned. No planks less than 12" in width will be permitted to be used unless it is to make up the difference in size of the board required. Only the lap joints should be adopted in all cases. Lamp holders, ceiling roses, control switches, covers, etc., should be of reinforced bakelite material.

5. The undersigned reserves the right to reject the tenders without assigning any reasons therefor.

6. The successful tenderer will be required to deposit an earnest money of Rs. 220 (Rupees Two hundred and twenty only) and execute an agreement within a week from the date of intimation of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same and carry out the wiring following the rules of this department as well as that of the Institution of Electrical Engineers. He should also be prepared to adopt any change in the location of control points and other outlets that might be suggested by the undersigned during the progress of the work without extra cost if the tender is not materially affected by such deviations.

7. The undersigned reserves the right also to reject the work either in full or in part if he finds the work not carried out in terms of the specifications or is otherwise dissatisfied with the workmanship.

8. *Name of work.*—Installing electric lights, etc., to the Inspection Bungalow, European Kitchen, Indian Kitchen and running over head lines and installing ornamental lamp posts for yard lighting at Jog

9. *Last date for receiving tenders.*—31st October 1938, 3 P.M.

10. *Date and time of opening the tenders in public.*—31st October 1938 at 4 P.M.

11. A period of four weeks will be allowed for final completion of the work with effect from the date of final acceptance of the tender. A penalty of Rs. 10 (Rupees ten only) for each day's delay over and above the stipulated period during the first week and Rs. 20 (Rupees Twenty) during the 2nd week will be imposed. If there be further delay the department will take charge of the installation at whatever stage it might be and arrange for its completion through any other agency entirely at the risk of the tenderer.

12. It will be obligatory on the part of the tenderer executing the work to attend to any major troubles that might crop up due to bad workmanship, etc., during the first twelve months from the date of handing over the installation to this department without any return for services rendered.

13. *Details of work.*—The quantities given in the annexed statement are not guaranteed and are subject to variation at the time of executing the work.

DETAILS OF WORK.

Interior work and Mains.

Part I—Installing Electric Lights and Ceiling Fans to the Inspection Bungalow at Jog.

			Quantity
1.	Supplying, fixing and wiring in teakwood 2″×1″ two-way casing and capping treated with 2 coats of white lead using No. 10 and 12 B. & S. insulated wire, 2,500 M. O. grade for ⅝″ brass pendents 2 to 4′ long complete with brass ceiling plates flexible cord, B. C. lamp holder, 5 amp. switch and one 5 amp. bakelite bow cutouts and accessories	No.	10
2.	Supplying, fixing and wiring ceiling fans 220-230 volts 25 cycles—52″ sweep with 3 alluminium curved blades complete with shackle, hook canopy, standard length of dowo rod and 5 point variable speed choke type regulator suitable with hollow spindle, finished in white with gold lines using suitable suspension clamps, etc., as per specification *vide* Item No. 1	,,	5
3.	Supplying, fixing and wiring ornamental lamp fittings provided with 14″ dia., white opal superlux glass Globe Pendent with Antique Brass Metal work, arranged for 200 to 300 watts, Osram lamps similar to G. E. C. Cat. No. F. 14513 complete with brass ceiling plate, canopy 3 to 5′ long by ⅜″ brass tube as per specification *vide* Item No. 1	,,	5
4.	(Please quote separately for supplying, fixing and wiring the above specified ceiling fan and ornamental lamp fittings such that the lighting fixture should be rigidly attached underneath the ceiling fan so as to combine Item No. 2 and 3 as one item)	,,	5
5.	Supplying, fixing and wiring for water tight fittings complete with cast iron enamelled reflector, B. C. lamp holder, goose-neck, well-glass, etc., as per specification, *vide* Item No. 1	,,	4
6.	Supplying, fixing and wiring combined wall plug with switch and nipple, bakelite 10 amp. face entry as per specification, *vide* Item No. 1	,,	1
7.	Supplying, fixing and wiring combined wall plug with switch and nipple bakelite 5 amp. face-entry as per specification *vide* Item No. 1	No.	5
8.	Supplying, fixing and wiring with No. 10 and 12 B. & S. Insulated wire—2,500 M. O. grade —1 teakwood board 30″×21″×1″ with 2″ battens and rear board coated with 2 coats of white lead equipping it with a 30 amp. D. P. S. T. Iron clad switch with fuses and one 3-way, double pole, home office pattern "Neata" 10 amp. per way, iron clad distribution box with 10 amp. circuit switches using necessary accessories and running mains about 20′ in ¾″ conduit pipe using No. 10 B. & S. insulated wire 2,500 M. O. grade from the outside pole to the switch board with necessary accessories	,,	1
9.	Supplying and fixing 12″ shades fancy glass of approved pattern similar to G. E. C. Cat. No. F.4352	,,	10
10.	Supplying and fixing lamps 40 to 100 watts 230 volts	,,	14
11.	Supplying and fixing Osram lamps 200 to 300 watts—230 volts, suitable for Item No. 3	,,	5
12.	Supplying and fixing Lamp locks	,,	9
13.	Earthing the Iron Clad switches and Mains	Item	1 L.S
	Part I—Total ..		

Part II—Installing Electric Lights to the European Kitchen.

Interior Works and Mains.

1.	Supplying, fixing and wiring in teakwood 2″×1″ two-way casing and capping coated with 2 coats of white lead using No. 12 B. & S. insulated wire 2,500 M. O. grade for drop lights complete with 2 plate bakelite ceiling roses, flexible cord, B. C. C. G. bakelite lamp holder and 5 amp. bakelite control switch—one 5 amp. bakelite bow cutout and accessories	No.	4

Item			Quantity
2.	Supplying, fixing and wiring Oxidised fancy copper brackets 9″×½″ as per specification above	No.	4
3.	Supplying, fixing and wiring water tight fittings complete with gooseneck, Cast Iron enamelled reflector, B. C. lamp holder and well glass, etc., as per specification, *vide* Item 1	,,	1
4.	Supplying, fixing and wiring combined wall plug with switch and nipple, bakelite, 10 amp. face entry as per specification, *vide* Item No. 1	,,	4
5.	Supplying, fixing and wiring one teakwood Board 12″×12″×1″ with 2″ battons and rear board equipping the same with a 15 amp. D. P. S. T. iron clad switch with fuses using No. 12 B. & S. insulated wire 2,500 M. O. grade and running mains about 20′ in ⅝″ braized conduit pipe from the outer rigger to the main board with necessary accessories using No. 12 B. & S. insulated wire 2,500 M. O. grade	,,	1
6.	Supplying and fixing fancy glass or enamelled shades of approved pattern ..	,,	8
7.	Supplying and fixing lamps 40 to 60 watts,—230 volts	,,	9
8.	Earthing the iron clad switch and main pipe	Item 1	L.S.
	Total—Part II ..		

Part III—Installing Electric Lights to the Indian Kitchen.

Interior work and mains.

1.	Supplying, fixing and wiring in Teakwood 2″×1″ two-way casing and capping, coated with two coats of white lead using No. 12 B. & S. insulated wire 2,500 M. O. grade drop lights complete with two plate bakelite ceiling roses, flexible cord, B. C. C. G. bakelite lamp holder and 5 amp. bakelite control switch and 5 amp. bakelite bow cut out and other accessories	No.	2
2.	Supplying, fixing and wiring oxidised fancy copper brackets 9″×½″ *vide* specification item 1	,,	3
3.	Supplying, fixing and wiring water-tight fittings complete with gooseneck, C. I. enamelled reflector B. C. lamp holder, and well glass, etc., as per specification *vide* item No. 1	,,	2
4.	Supplying, fixing and wiring combined wall plug with switch and nipple, 10 amp. bakelite face entry, as per specification *vide* item No. 1	,,	1
5.	Supplying, fixing and wiring one teakwood Board 12″×12″×1″ with 2″ battons and rear board, equipping the same with a 15 amp. D. P. S. T. ironclad switch with fuses and running mains about 20 ft. in ⅝″ braized conduit pipe from the outside pole to the switch board with necessary clamps, etc., using No. 12 B. & S. insulated wire 2,500 M. O. grade	,,	1
6.	Supplying and fixing fancy glass or enamelled shades of approved pattern ..	,,	5
7.	Supplying and fixing lamps 40 to 60 watts—230 volts	,,	7
8.	Earthing the ironclad switch and main pipe	Item 1	L.S.
	Total—Part III ..		

Part IV—Running over head lines and installing ornamental Lamp Posts.

Exterior work.

1.	Supplying, fixing and tarring S. M. rails, 24′ long 41¼ lb. section	No.	15
2.	Supplying and fixing 2 pin D. C. A. with clamps, distant pipe pieces, bolts, etc., complete for the above rails	,,	10
3.	Supplying and fixing 2-pin S. C. A. with clamps, bolts and nuts, etc., for the above rails	,,	10
4.	Supplying and fixing 4 pin D. C. A. with clamps, bolts and nuts, etc., for the above rails	,,	2
5.	Supplying and fixing 4 pin S. C. A. with clamps, bolts and nuts, etc., complete for the above rails	,,	2
6.	Supplying and fixing guy sets complete with anchor guy road and 7 strand guy wire	Sets	10
7.	Supplying and fixing insulators Low tension distribution type, 8,000 V ..	No.	84
8.	Supplying and stringing copper wire 6 B. & S. bare hard drawn	Lbs.	465
		Ft.	5,800
9.	Supplying and laying No. 12 B. & S. twin conductor, paper insulated, lead covered, underground cable suitable for 1,000 volts pressure in a trench 3′ deep and surrounding the same with 3″ of fine sand, enclosing the ends of cable in outdoor type cast iron junction boxes filled with insulating compound and connecting up the same with the over head feeder line with proper length of 1½″ galvanised iron pipe 15 to 18 feet long for running the vertical length of cable on the poles, well supported with the necessary clamps, etc., complete	Ft.	800

Item	*Quantity*
10. Supplying, fixing and wiring cast iron Ornamental lamp posts fluted type, on a cement concrete foundation 2′×2′×2′ fixed with $1\frac{1}{2}'\times\frac{3}{8}''$ bolts and providing it with the Bangalore type Ornamental lamp fittings (design to be approved by the Department) with the necessary fixture, lamp holder, using necessary underground C. I. junction boxes 2 and 3 way, No. 12 B. & S. twin conductor, lead covered, cable 5 amp. D. P. Bakelite control switch, water proof, protected with 2 of 5 amp. fuse cutouts, water proof, housed at the base of the lamp post, and other necessary accessories. (This excludes the cost of fluted type ornamental lamp posts, which will be supplied by the Department as they are already available at Jog)	No. 10
11. Supplying and fixing lamps 100 to 200 watts, 230 volts for the above	,, 10
12. Earthing	L. S.
Total—Part IV	

Y. RAMAŚWAMI,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 29th September 1938.

Attention of the public is drawn to the Notification, calling for tenders for the Improvement of cart-track from Hoisalakatte on the Banavar-Sira Road to Dasodi and on to join Huliyar-Hiriyur Road in page 1752, Part VI of the *Mysore Gazette*, dated 13th October 1938.

2. Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M., on 25th October 1938.

3. Earnest money required for the work is Rs. 325, which should be credited to the Treasury to the head "17 (*a*) Public Works Deposits" and the treasury challan enclosed.

Abstract Notification dated 29th September 1938.

1. Attention of the public is drawn to the Notification, calling for tenders for the Restoration of Konankere Minor Tank, Gubbi Taluk, in pages 1753-1754, Part VI of the *Mysore Gazette*, dated 13th October 1938.

2. Tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M. on 25th October 1938.

3. Earnest money required for the work is Rs. 335 which should be credited to the treasury and the treasury challan enclosed.

P. RAJAGOPALAN,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 17th September 1938.

The attention of the public is hereby invited to the advertisement on pages 1698-1701, Part VI of the *Mysore Gazette*, dated 6th October 1938, calling for tenders for the work of constructing a Combined Dispensary for Men and Women at Chamarajnagar.

B. KRISHNA RAO,
Executive Engineer.

OFFICE OF THE SUPERINTENDING ENGINEER, IRRIGATION CIRCLE, K. R. S. WORKS.

Notification dated 14th October 1938.

Applications are invited from candidates who are graduates in Engineering (Civil or Mechanical) for appointment as Work Inspector on Rs. 50 per mensem for the subordinate supervision of the Shimsha Branch Works (Irwin Canal).

2. The appointment is borne on the Work Establishment of the Division and is purely temporary and terminable without notice.

3. The applications should be in the form prescribed by the Central Recruitment Board, and should reach the undersigned on or before the 7th November 1938.

4. The appointment is open to candidates of Backward Communities only.